# SEAS Homes


H SEAS

<sup>•</sup>NxtGen Construction Technology for Fast, Permanent, Premium finished & Strong Structures<sup>2</sup>

# WHAT IS SEAS HOMES TECHNOLOGY ?

- "Light Guage Steel Framing" is construction technology where cold formed steel is used as construction members.
- Entire building is constructed with individual cold formed steel panels like walls, roofs, decks, beams etc.
- All panels are manufactured in factory with high precision as per structural drawings.
- Pre-fabricated steel brought to site and assembled as per assembly drawings to make individual panels walls, roofs, joists etc.
- Assembled panels are erected sequentially to construct entire structure.
- Post that structural cladding work is done.





ASSEMBLY

### MANUFACTURING




FINISHING



WALL PANEL FITTINGS ERECTI ON


## LGSF VS CONVENTIONAL PREFABRICATED STRUCTURE

SPECIFICATION	MS FARBICATED STRUCTURE	LGSF STRUCTURE	BENEFIT OF LGSF
GRADE	E250	E550	Reduced weight of overall structure
COATING	POST FABRICATION COATING REQUIRED	150GSM COATING	Better performance in extreme weather condition even if exposed
MANUFACTURING	MANUAL	AUTOMATIC	Higher accuracy in construction & reduced site execution time
CONNECTION	WELD OR BOLT	SCREWS OR RIVET	Very less site connection activities
ERECTION	CRANE OR HYDRA	HUMAN	Easy to erect the structure
LOAD DISTRIBUTION	FRAME STRUCTURE	LOAD BEARING SYSTEM	Uniform distribution of load & less offsets of internally, more carpet areas




# Design, Manufacturing and Erection Stages






Working Drawing



Structural Design & Detailing





Assembly & Erection




Steel Production as per design



**Machine File & Production** 

# WHY TO CHOOSE SEAS HOMES






## Professional & Skilled siteteam



•



No Bricks, Cement, water, sand Required



• All factor made Material with high precision and control



Premium Quality finishing





# DISADVANTAGES

- EARLY INVESTMENT IS HIGHER
- PRE-CONSTRUCTION PLANNING IS VERY IMPORTANT
- POST CONSTRUCTION CHANGES ARE
  VERY DIFFICULT
- VIBRATING EQUIPMENT SHOULD BE DAMPED OR PROVISIONS NEEDS TO BE DONE
- PRECISE DRAWINGS ARE EXPECTED
- UNPLANNED LOADS SHOULD BE PLACED CAREFULLY.

# **Components of SEAS Homes:** Galvalume Steel







## HOUSE OF STEEL : Walls, Roofs, slab joists

Light Gauge Steel is cold formed Galvalume steel AZ150 G550. It is:

- ✓ Strong: 550 MPA yield strength
- ✓ **Durable**: Exceptional Corrosion & Weather resistance
- ✓ Light Weight: 5 to 8 times lighter house than conventional
- Recyclable: Without losing its virtues it can be recycled infinite times
- ✓ **Reusable**: Could be dismantled and erect again at desired location
- ✓ **Quality:** Advanced Australian Manufacturing unit
- ✓ Functionality: Sections are manufactured with the provisions for Electricity Conduits and & holes for the connections
- ✓ This high performance steel is used at every 1, 1.5 or 2 feet as per the design requirements

# Components of SEAS Homes: <u>Fibre Cement</u> <u>Boards</u>





## Where do we use FCB?

- External Walls, Internal Walls
- Heavy Duty Boards for Slab
- > As Cladding on the walls
- > Roofing, Roof underlays

## Why we use FCB?

- □ Impact Resistant
- □ Moisture Resistant
- **D** Termite Proof
- □ Fire Resistant
- □ Sustainable



# Components of SEAS Homes: <u>Rockwool</u> <u>Insulation</u>







## Why Insulation?

- ✓ Non combustible and Fire Resistance
- $\checkmark\,$  Noteworthy Thermal resistance
- $\checkmark\,$  High Sound Absorbent
- ✓ Biologically Inert
- ✓ Non Hazardous
- ✓ Environment Friendly
- ✓ No Aging Effect

# **Components of SEAS Homes:** <u>Vapour Barrier</u>





## Why Vapour Barrier?

✓ Excellent Resistance to water

Permeance

- ✓ Chemical Resistant
- ✓ Rot Proof
- ✓ Bacteria Resistant
- ✓ Long Life



# Multi-Layered Waterproofing by SEAS Homes



#### WALLS

- Corners & Joints by PU Elastomeric
  Sealant
- 2. Fiber Tape
- 3. NCL Spray jointing Plaster
- 4. Damp Proof by Asian Paints

#### BATHROOM WALLS

- 1. Corners & Joints by PU Elastomeric Sealant
- 2. Synthetic Resin Liquid as Primer
- Deformable, Cement based with Elongation properties Adhesive Suitable for any tiles including Natural Stones
- 4. Vapour Barrier on other side of walls

#### BATHROOM FLOOR

- Corners & Joints sealed by PU Elastomeric Sealant
- 2. Coving by Bituminous Sealing Tape
- 3. Bonding Primer
- PU Waterproofing compound in grid application
- Deformable, Cement based with Elongation properties Adhesive Suitable for any tiles including Natural Stones




#### TERRACES

- . Corners & Joints by PU Elastomeric Sealant
- 2. Coving by Bituminous Sealing Tape
- 3. Primer
- 4. 2 coats of PU/Acrylic Compound
- 5. 2 coats of Damp proof
- 6. Concrete Screeding/Tiles




# **Options offered** for External Wall Sections



- 2 Staggered Layers of 8+8 mm =16 mm FCB OR
- 1 layer of 8 mm FCB + Cladding of Designer Boards or Planks OR
- 1 layer of 12 mm FCB

## **Option 1: Standard Budget**

# **Options offered for External Wall Sections**




## What is EIFS?

## Option 2: Premium Budget



# **Options offered for Internal Wall Sections**






## Wet Areas

## Dry Areas

# **Slab and Roof Sections**





## SEAS HOMES TECHNOLOGY















# BUNGALOW EXTENSIONS PROJECTS



Area – 2700 sqft Time to completion of Cold Shell – 90 days Challenges – Less place around building, Double Height walls Reason to choose SEAS HOMES – Light Weight, Dry Construction, Performing House, Faster, No use of concrete and water





#### Extension of the house for Mr. Shedge at Satara







Area – 1100 sqft (Turnkey Project) Time to completion of Cold Shell – 60 days Challenges – Lockdown, less place around building Reason to choose SEAS HOMES – Light Weight, Faster, No use of concrete and water, Performing House,

#### Extension of House/Hospital for Dr. Sukale at Mahad, Raigad





Area – 1200 sqft Time to completion of Cold Shell – 40 days Challenges – Lockdown, Rainy Season, 4<sup>th</sup> floor extension Reason to choose SEAS HOMES – Light Weight, Faster, No use of concrete and water

#### Extension of 30 year Old House for Mr. Rathod





Area – 1000 sqft Time to completion of Cold Shell – 40 days Challenges – Lockdown, Rainy Season Reason to choose SEAS HOMES – Light Weight, Faster, No use of concrete and water



#### Extension of House for Mr. Sawant at Satara







Area – 800 sqft (Turnkey Project) Time to completion of Cold Shell – 45 days Challenges – 3<sup>rd</sup> floor Extension, No place around the building Reason to choose SEAS HOMES – Professional Team, Performing House, Faster Construction, No Concrete

# PRIVATE RESIDENTIAL & COMMERICAL PROJECTS

## A small Farmhouse at Diskal, Satara







Area – 1800 sqft Time to completion of Cold Shell – 60 days Challenges – Lockdown and Remote & Hilly place Reason to choose SEAS HOMES – Faster, Economical, No use of water , Hassle Free experience

#### Weekend Villa for Mr. Patil near Velhe, Pune







Area – 1700 sqft (Turnkey Project) Time to completion – 90 days Challenges – Remote place Reason to choose SEAS HOMES – Faster, Hassle free experience, Performing House, Professional team,

### Roof for Mr. Patil Residence at Kolhapur



Area – 4300 sqft (turnkey Project) Time to completion of Cold Shell – 90 days Challenges – Complicated Design of roof Reason to choose SEAS HOMES – Anti corrosion steel, Light Weight, Faster



#### Weekend Private Villa for Mr. Nikam in Girivan near Mulsi







Area – 3000 sqft (turnkey Project) Time to completion of Cold Shell – 60 days (finishing work ongoing) Challenges – 40ft long roof, complicated design Reason to choose SEAS HOMES – Performing House, Faster, professional team, hassle-free experience



Weekend Small Villa for Mr. Kumar (Ex-chief Secretery of MS) at Pune



Area – 1200 sqft (two Structure) Time to completion of Cold Shell – 60 days (Finishing work Ongoing) Challenges – Disrupting flow Electricity Reason to choose SEAS HOMES – Economical, Faster





Retirement Home for Mr. Ashish Kumar at Pali Hill City, near Khopoli





Area – 1700 sqft (Turnkey Project) Time to completion of Cold Shell – 45 days Challenges – Remote place Reason to choose SEAS HOMES – Professional Team, Performing House, Faster Construction

### Dairy Processing Unit at Pirangut for Yellow Slice








Area – 3300 sqft (Turnkey Project) Time to completion of Cold Shell – 70 days Challenges – Retaining wall done in LGS system Reason to choose SEAS HOMES – Fast Construction





#### Area – 1500 sqft

Time to completion of Erection– 10 days Challenges – Remote place, Unique Design Reason to choose SEAS HOMES – Professional Team, Performing House, Faster Construction



### Villa for Mr. Gaikwad at Sangola





Area – 1500 sqft (Turnkey Project) Time to completion of Cold Shell – 42 days Challenges – Use of Concrete panel as external cladding Reason to choose SEAS HOMES – Fast & durable construction









### HYDERABAD PROJECT





# ALIBAUG PROJECT



SIKKIM PROJECT

### LAWASA PROJECT















CIIIT Project at Gadchiroli









# MODULAR HOUSE – LIFT & SHIFT





### **BEAUTIFUL FINISHED ROOF TOP Extension INSIDE & OUT**











### **BEAUTIFUL FINISHED ROOF TOP Extension INSIDE & OUT**






# **Our Ongoing Projects**



- 1. 18000 Sqft CIIIT (Institutional Building) Unit at Gadchiroli
- 2. 13000 sqft apartment building at Sikkim
- 3. 9000 sqft dormitory for School at Arunachal Pradesh
- 4. 2500 sqft mockup hotel for Saint Gobain at Delhi
- 5. 2500 sqft private villa for Mrs. Thatte at Beverly hills near Shahapur, THANE (TUNKEY)
- 6. 3500 sqft Mansion (Old Fashioned Wada) for Mr. Belsare at Girivan near Mulsi, PUNE (TURNKEY)
- 7. Luxurious Villa 1800 sqft at Alibaug for Mr. Mandlik
- 8. 2000 sqft Luxurious villa for Organo Antharam



### SOME OF OUR CLIENTS















ARTISANAL CHEESE






Inspired by Villages



## SUMMARY OF SEAS HOMES WORK

- Total Project Executed in 2021/22 8
- Total Project Executed in 2022/23 16
- Ongoing Projects 68500 sqft
- **Completed Projects** 33784 sqft
- Average time required for one project 51 days
- Total Employees in Team 25
- **Our Clients** TATA, Malpani Group, VKV, Teesta Urja, Modulous Housing, Yellow Slice, Organo Eco-Habitants, etc








www.seashomes.com

seashomes@gmail.com



seashomes

seas\_homes

SEAS Homes